

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

Name of work :- वार्ड कं. 70 अन्नपूर्णा मंदिर प्रांगण के समीप पेवर ब्लॉक लगाने का कार्य।

S.No.	Description and details of work	As per Building SOR 01.01.2015	
		Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	70.8	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	47.2	cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm subble mould	472	sqm
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	15.4816	cum
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	70.8	cum


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI