MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम:- वार्ड कं. 67 सेक्टर 08 सड़क 05 में व्हालीवाल कोर्ट निर्माण कार्य।

As Per Building SOR 01.01.2015 & Non Sor Item

S.N.	Description and details of work	Qty.	Unit
I	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types	48.43	cum
2	of soils.) Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	24.07	cum
11	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:(A) Foundations, footings, base of columns and plinth beam in any shape and size. Footing	10.20	sqm
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20mm nominal size).	36.58	cum
	@ Rs. 4073.00/m3 Providing and fixing approved pipe hand rail by welding to iron railing including applying a priming coat of red oxide zinc chromate primer. M.S Pipe	35.21	kg
5	Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass. Captivating design Vivacious colors Beautiful	240	sqm
6	LED MODULE 300watts (2year warranty) housing,blacksilver (bajab,havels etc.) AC90-350V,50/60HZ,PFC>0.95,100-135LM/W	0	each
5	Cosco sports cotton (9.5) meter volleyboll net cosco sports (cotton)	1	each

EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI

ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI

SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI