


MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम:- स्वच्छ सर्वेक्षण 2022 अंतर्गत नगरीय निकायों में रोड पोर्ट होल मरम्मत कार्य

S.N	Particulars	Unit	Qty.	Rate	Amount
1	Filling Pot-holes and Patch Repairs with Close Graded Premix Surfacing / Mixed Seal Surfacing, 20mm. (Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot-holes with hot bituminous material as per clause 512, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 i/c tack coat.)				
		Sqm	5183		
2	Repair of joint Grooves with Epoxy Mortar Repair of spalled joint grooves of contraction joints, longitudinal joints and expansion joints in concrete pavements using epoxy mortar or epoxy concrete)				
		Mtr	500		
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm				
	Plain/ normal coloured precast interlock concrete block	Sqm	2300		

- 
 सहायक अभियंता
 नगर पालिक निगम
 भिलाई