

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 50 शास्त्री नगर के विभिन्न स्थानों पर पाईप लाईन बिछाकर संधारण कार्य।

(As Per PWD Building SOR 01.01.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	a) 50 mm dia. nominal bore	250.00	Metre
	b) 40 mm dia. nominal bore	180.00	Metre
	c) 32 mm dia. nominal bore	135.00	Metre
	d) 25 mm dia. nominal bore	120.00	Metre
2	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):		
	a) 50mm. nominal bore.	15	Each
	b) 40 mm dia. nominal bore	7	Each
	c) 32 mm dia. nominal bore	7	Each
	d) 25 mm dia. nominal bore	5	Each
3	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete:		
	a) 50 mm nominal bore	15	Each
	b) 40 mm dia. nominal bore	7	Each
	c) 32 mm dia. nominal bore	7	Each
	c) 25 mm dia. nominal bore	5	Each
4	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	20	Each


Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai