

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 44, लक्ष्मीनारायण नगर के विभिन्न पूर्व निर्मित नालियों का स्लोप संधारण कार्य।

(As Per PWD Building SOR 01.01.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	66.72	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. + Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water.	83.40	Cum
3	Carriage by mechanical transport upto 5 km lead: Sludge	66.72	Cum



Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai