

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 38 सोनिया गांधी नगर प्रगति मार्केट के पीछे से केनाल रोड़ तक नाला सफाई एवं संधारण कार्य।

(As Per PWD Building SOR 01.01.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	7.65	Cum
2	Pumping out water caused by springs tidal or river seepage, broken water main or drains and like during Excavation or during Excavation and laying of base concrete (volume to be calculated taking height from water level to bottom of pit and to be measured and paid) .	108.00	Cum
3	Extra for laying PCC/ RCC, in or under water or liquid mud including cost of pumping or bailing out of water and removing slush etc. complete:	54.00	Cum
4	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	52.50	Cum
5	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	5.25	Cum
6	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	94.00	Sqm
7	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	20.93	Cum
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	837.00	Kg
9	Providing and laying nominal mix Plain cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	18.30	Cum
10	Carriage by mechanical transport for 5 km lead. Earth	177.72	Cum

Executive Engineer  
Municipal Corporation  
Bhilai

Assistant Engineer  
Municipal Corporation  
Bhilai

Sub-Engineer  
Municipal Corporation  
Bhilai