

MUNICIPAL CORPORATION OF BHILAI

NIT


वार्ड क्र० 30 प्रगति नगर 18 नं. रोड आगनबाडी के पास मुख्यमंत्री सस्ती दवाई दुकान का संधारण कार्य।


(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020, NON SOR Item)


S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	35.55	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	9.38	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	26.9	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	2152.00	Kg
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	441.6	Sqm
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, Pillars, Piers and likes- rectangular or square in shape	52.80	Sqm
7	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Beams, lintels, cantilevers & walls	24.00	Sqm
8	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	26.00	Sqm
9	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	35.86	Cum
10	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	3.6	Cum
11	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	3.38	Cum
12	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	56.00	Sqm
13	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	60.39	Sqm
14	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	90.00	Sqm
15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	168.3	Kg

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
16	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	168.3	Kg
17	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer. Electric resistance or induction butt welded tubes Grade-250	437.58	Kg
18	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	57.5	Sqm
19	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	1.34	Sqm
20	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even. As Per Plaster	33.00	Sqm
21	Supplying and fixing rolling shutter of approved makes made of M.S. laths interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and out side locking with push and pull arrangement complete but excluding the cost of top cover and spring. 80x1.25mm M.S. Laths	21.78	Sqm
22	Providing and fixing 27.5cm long wire spring for rolling shutters.	2.00	Each
23	Providing and fixing M.S. sheet top cover for rolling shutter 1.25mm thick	2.01	Sqm
24	Providing and fixing M.S. sheet top cover for rolling shutter Providing and fixing ball bearing for rolling shutters.	2.00	Sqm
25	Providing and fixing mechanical device chain and crank operation for operating rolling shutters.	1.00	Set
26	Supply and fixing of pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	33.5	SQM

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
27	Providing and fixing 97mm thick Gypsum board partition upto ceiling height consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120, consisting of floor and ceiling channel 50mm wide having equal flanges of 32mm and 0.55mm thick fixed to the floor and ceiling at the spacing of 610mm centre to centre with dash fastener of 12.5mm diameter 40mm length and the studs 48mm wide having one flange of 34mm and other flange 36mm and 0.55mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610mm centre to centre by 6mm dia bolts and nuts at both ends of partition fixed flush to wall with rawl plugs at spacing of 450mm centre to centre and fixing of boards to either side of frame work by 25mm dry wall screws on studs, floor and ceiling channels at the spacing of 300mm centre to center and 97mm thick Gypsum board which includes one layer of tapered edge 12.5mm thick Gypsum plaster board (conforming I.S. 2095-1982) screw fixed with 25mm screws at 300mm centre to centre to either side, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, joint finisher and two coats of primer suitable for board as per manufacture's specification and Direction of Engineer-in-charge all complete.	72.00	SQM
28	White washing with whiting to give an even shade. On new work (Three or more coats)	33.00	Sqm
29	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) :Ordinary cement without any pigment	35.64	Sqm
30	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	90.00	Sqm
31	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	116.39	Sqm
32	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	5.61	Sqm
33	Electrical & Sanitary Work Lum_Sum As Per Electrical SOR	1	Job
34	Non SOr Item - Providing and Fixing Glow Shine Board with Fram including fixing charge, designing charge, labour charge transporting charge etc.	60.00	Sqft


कार्यपालन अभियन्ता
नगर पालिक निगम, मिलार्ड


सहायक अभियन्ता
नगर पालिक निगम, मिलार्ड


उप अभियन्ता
नगर पालिक निगम, मिलार्ड