


MUNICIPAL CORPORATION OF BHILAI


NIT

कार्य का नाम :- वार्ड कं. 64,65,66 एवं 67 के विभिन्न स्थानों में पेवर ब्लॉक का संधारण कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or <u>for any other purpose including disposal</u>	80.26	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	39.22	Cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	401.31	SQM
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.93	Cum
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	70.97	Cum


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI