

9

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम – उच्चस्तरीय जलागार में स्थित वॉल्व चेम्बर संधारण कार्य।

S.N.	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains orfor any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	In all types of soils.	50	20	1.5	0.5	750	cum		
2	Providing and making 12mm thick cement plaster of mix:								
	In Cement Mortar 1:4 (1 cement : 4 fine sand)	200	2	2		800	Sqm		
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	40	0.5	0.5	1.5	15	Cum		
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	Thermo-Mechanically treated bars FE 415				50		kg		

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

अभियन्ता
नगर पालिक निगम, भिलाई