MUNICIPAL CORPORATION BHILAI (C.G.) NIT

Name of work :- वार्ड कं. 64 सेक्टर 10 में जयंती स्टेडियम क`समीप शौचालय

As per Building SOR 01.01.2015 ELEC SOR 2020,&NON SOR

NO.	PARTICULARS	QTY.	UNIT
1	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	56.70	Sqm
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	44.94	Cum
3	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M, and lift upto 1.5 M.	44.94	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.		
	1:4:8 (1 cement : 4coarse sand : 8 graded stone aggregate 40mm nominal size).	3.82	Cum
5	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork.	1.91	Cum
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	8.17	Cum
7	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	11.56	Cum
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	19.20	Cum
9	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:	612.75	Kg
10	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
47.1	Foundations, footings, base of columns and plinth beam in any shape and size.	67.60	Sqm
11	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:	-	
The last	Columns, Pillars, Piers and likes- rectangular or square in shape	26.40	Sqm
12	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	Weather shade, chhajja, Cornices and mouldings (Pg-16, Code No-2.1.14)	3.84	Sqm
13	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:	1	
	Beams, lintels, cantilevers & walls	13.08	Sqm
14	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc.	A	
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	55.20	Sqm
15	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in:		89
16	Cement Mortar 1:6 (1 cement : 6 coarse sand) Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in:	7.38	Cum
	Cement Mortar 1:6 (1 cement : 6 coarse sand)	13.95	Cum
17	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought framed and fixed in position.		100

Is	Sal, bijasal, benteak, khair, haldu	0.12	Cum
	Providing and fixing flush door shutters decorative type, core of block board construction with frame		1
18	of first class hard wood and well matched teak ply veneering with vertical grains or cross bands and		7
f	face veneers on both faces of shutters excluding hinges.	- 1	Cam
3	35 mm. thick (single leaf)	13.14	Sqm
19 F	Providing and fixing bright finished brass butt hinges with brass polished MS screws complete:	7 D.	
	100x85x5 50 mm (Heavy Type)	9.00	Each
10	Providing and fixing bright finished brass sliding door bolt with nuts and brass polished MS screws		
	complete	2.00	Each
12	250x16mm	2.00	
21	Providing and fixing brass door latch with brass polished MS screws complete:	2.00	Each
. :	250x16x5 mm	2.00	Luon
22	Providing and fixing bright finished brass tower bolts (barrel type) with brass polished MS screws		
	complete:	12.00	Each
10	200x10mm		
23	Providing and fixing bright finished brass door handles with brass polished MS screws complete:	2.00	Each
	125 mm	8.00	Lacin
1,1	Making the opening in brick masonry for door/ window/ clerestory window		
- 1	including dismantling in floor or walls by cutting masonry and making good		
24	the damages to walls, flooring and jambs complete to match existing	-	
	surface i/c disposal of malba/ rubbish to the nearest municipal dumping		ALL P
	ground. Float glass panes of thickness 5.5 mm	13.14	Sqm
	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and		
25	languing a priming coat of red oxide zinc chromate primer.	050.00	kg
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	250.00	Ng
	Providing and laying vitrified floor tiles with soluble salt printing, of size		
	600x600mm with water absorption less than 0.5% and conforming to IS		
26	: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1		
	cement : 4 coarse sand) including grouting the joints with white cement		
	and matching pigments etc. complete Size 600x600mm	48.00	Sqm
	Size occasionini		
	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622		
	of approved make, colours, shades and size on wall and dados over 12		
27	mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and		
	jointing with grey cement slurry @ 3.3kg per sqm including pointing in		
	white cement mixed with matching pigment complete. Size above 200x300mm	94.08	Sqm
28	6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	15.00	Sqm
	12mm thick cement plaster of mix:		
29	In Cement Mortar 1:6 (1 cement : 6 fine sand)	134.40	Sqm
	IN Cement Mortal 1.0 (1 Cement , 0 line sand)	104.40	
	15mm thick cement plaster on the rough side of single or half brick wall of mix:		
30	15mm trick cement plaster on the rough side of single of than brick wall of this.	106.08	Sqm
-	In Cement Mortar 1:6 (1 cement : 6 fine sand)	161.40	Sqm
31	Applying one coat of cement primer on wall surface.	101.40	Sqin
	Wall painting with acrylic luxury emulsion (plastic) paint of required shade		
	to give an even shade. On new work (two or more coats)	161.40	Sqm
	Painting on new work (two or more coats) to give an even shade with		
		15.00	Sqm
	Satin synthetic enamel paint		
	Structural steel work in single section including cutting, hoisting, fixing in	120.00	KG
34 1	position and applying a priming coat of red oxide zinc chromate primer Providing and applying plaster of paris putty over plastered wall surface		ap44.907
34	ELIMINATE AND ANDROUGH DIANEL DI DOUG DUM STOL PROTOCO SELLOS	and the latest the state of the	
35	including scaffolding complete		
35	including scaffolding complete	15.00	Sqm
35	including scaffolding complete Lipto 2 mm thickness to make surface even and smooth in line and level.	15.00	Sqm
35	including scaffolding complete	15.00	Sqm

L. LAN			
The state of the s	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle	24.00	Sqm
37	iron posts including securing and screwing with Zmith dia G.f. Wiley staples, G.f.U-nails or steel pins etc., complete.	24.00	,
	f0 f0		1 1
	9.43.1 Aperture 50x50mm Providing and fixing mirror of superior glass (of approved quality) and	3.00	SQM
38	of required shape and size with plastic modified frame of approve	0.00	
30	make and shade with 6 mm thick hard board backing.		
	18.30.1 5mm thick mirror		
	Providing and fixing glass panes in glazed or paneled and glazed shutters	2.00	SQM
39	of doors and window, clearstory windows etc (Only area of glass panes to		
	be measured).		
	8.11.1 4mm thick Providing and fixing aluminium composite panels in approved panel sizes, (Frame)		
	thickness and shape on aluminium frame work on face of building. (Frame	14.00	SQM
40	thickness and snape on authinium name work or research		
	to be paid separately)		94F.
	9.61.1 3mm thick Providing and fixing laminated glass sheet of 8.76mm thickness in	3.15	SQM
	approved sizes on aluminium frame work on face of building. (Frame to be	3.10	
	paid for separately		36
	Supplying and stacking of good earth at site including royalty, loading,	10.00	Cum
41	unloading and carriage upto 5 km (earth measured in stacks will be	10.00	7.4
41	and by 20% for payment)	157	-
	Spreading of sludge, dump manure or/and good earth in required	10.00	Cum
42	thickness (Cost of sludge, dump manure or/ and good earth to be paid		7-12
72	and the last of th		1.00
	Draviding and planting following herbs in garden including preparation of	12.00	Sqm
43	soil, base plantation, providing and spreading different fertilizers, soil and		A SECTION
	Loans to see a fund day aloned		-
1.8	Providing and laying nominal mix plain cement concrete with crushed		Cum
	stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm	2.52	Cum
44	excluding cost of form work.1:172.3 (1 certient : 172 course sand : 9 g. sand		1
	nominal size).		RS 10841
111	WATER SUPPLY ,PLUMBING FOR FOUNTAIN		
			RS 8130
	ELECTRIFICATION		
	NON SOR		
	High Speed Jet Of Warm Air With Low Noise Blower to Quick Dry Wet Hands		
	Power: 1800 W, Voltage: 200 - 240 V, 50 Hz	1.00	Each
1	Automatic Cut Off after approx 5-10 seconds to save power Material: ABS PLASTIC, White color, Size: 10*10*9 Inch		1
	Durable & Sleek Hi Gloss ABS Plastic Casing		
	Tissue Paper Dispenser M-Fold Wall Mount - White Wall mounted	1	1
	Idea for : Restaurant & Hotel toilets, Kitchen etc	4.00	Each
,	la series and a series are a series and a se	1.00	Each
2	Harmless to children, durability, dependability and barety.		1
	Promotes hygiene whilst helping manage costs through controlled dispersing		+
	Manual Sanitary Napkin Vending Machine		
	Accept 5Rs Coin		
	No need of electricity Width	1.00	Each
3			
1	57 cm Height 33 cm Depth 22 cm Weight10 kg Product Capacity Is 25n. Light Present Color Is Pink. Height Adjustable		
a turk	Shelves		

EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI

ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI

SUB ENGINEER
MUNICIPAL CORPORATIC
BHILAI