

(3)

## MUNICIPAL CORPORATION BHILAI

## NIT

कार्य का नाम:- वार्ड कं. 62 से. 08 मध्य सड़क 34 एवं 35 में उद्यान का संधारण एवं मरम्मत कार्य। (मूलभूत सुविधा)

S.N.	Particulars	No.	L	W	H/D	Unit	Qty.	Rate	Amount
1	Supplying and stacking of good earth at site including royalty, loading, and unloading and carriage up to 10 km (earth measured in stacks will be reduced by 20% for payment). (Page no. 204,Item no. 22.2)	0	47	2	0.5	Cum	47.00		
2	Supplying and stacking at site well decayed cow dung manure from approved source, including loading unloading and carriage up to 10km (manure measured in stacks will be reduced by 8% for payment): (Page no. 204,Item no. 22.4)	0	47	2	0.3	Cum	28.20		
3	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete:32 mm dia. nominal bore	0	0	0	0	mtr	200.00		
4	40 mm dia. nominal bore	0	0	0	0	mtr	200.00		
5	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	0	47	4	2.00	sqm	376.00		
6	On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	0	47	4	2.00	sqm	376.00		
7	Distemping with acrylic washable distemper to give an even shade.On old work (one or more coats)	0	47	4	2.00	sqm	376.00		
8	Providing and planting well developed and healthy (21 and above) ornamental plants with digging holes, soil filling and chemical and biological treatment like Ficus, cycas Chhatin,bottle Palm, Supari palm,musanda and avenue palm ,tree i/c six month maintenance till well Establissh.as directed by engineer incharge. (NON SOR ITEM)	0	0	0	0	No	50.00		
9	Providing and planting well established flowering and ornamental plants/shrubs like Nerium ,Bougainvilla ,Crotons,Vidhya etc. with digging holes and chemical treatment . i/c six month maintenance till well Establissh.as directed by engineer incharge. (NON SOR ITEM)	0	0	0	0	No	50.00		
10	Providing and planting well developed succulent healthy ornamental plants with digging holes and chemical treatment like Thuja,cycas,lolima etc. i/c six month maintenance till well Establissh.as directed by engineer incharge. (NON SOR ITEM)	0	0	0	0	No	50.00		
11	LED Module 200 watts (2 years warranty) Housing: Black/ Silver (Bajaj, Hevels, etc.) AC90-350V, 50/60HZ, PFC>0.95, 100-135LM/W CRI>75, 2700-6500K, IP67, 427X305X122mm. (Non SOR) @ Rs-24900.00/each (NON SOR ITEM)	0	0	0	0	No	2.00		

सहायक अभियंता  
नगर पालिक निगम  
भिलाई

उपअभियंता  
नगर पालिक निगम  
भिलाई