



MUNICIPAL CORPORATION, BHILAI
NIT

कार्य का नाम:- वार्ड क्रमांक 30 प्रगति नगर के विभिन्न स्थानों में जी.आई. पाईप लाईन
विस्तारीकरण कार्य।

(As per P.W.D. Building S.O.R. W.E.F. 01.01.2015)

S.No.	Details of Item	UOM	Quantity	Rate	Amount (₹.)
1	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:			-	-
	15mm dia. nominal bore (Page- 177, Item-19.9.1)	MTr	50.00	-	-
2	20mm dia. nominal bore (Page- 177, Item-19.9.2)	MTr	150.00	-	-
3	25mm dia. nominal bore (Page- 177, Item-19.9.3)	MTr	140.00	-	-
4	32 mm dia. nominal bore	MTr	100.00	-	-
5	Making connection of G.I. distribution branch in G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete: (Dia of main line to be measured) 50 mm nominal bore	Nos	9	-	-
6	Providing and fixing brass/gun metal gate valve with C.I. wheel of approved quality (screwed end): 50mm nominal bore.	Nos	5	-	-
7	Providing and fixing 15mm nominal bore Brass bib/stop cock of approved quality : Bib cock (350gram)	Nos	5	-	-
8	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore	Nos	2	-	-
9	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 32 mm nominal bore	Nos	3	-	-
10	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete:32 mm dia. nominal bore	Nos	2	-	-


कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई