

MUNICIPAL CORPORATION OF BHILAI
NIT

वार्ड क्र. 39 चं.शे.आ. नगर में विभिन्न स्थानों पर नाली निर्माण एवं आर.सी.सी. कव्हर लगाने का कार्य।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). (+) Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	85.05	Cum
2	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	7182.00	Kg
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size)	17.55	Cum
4	25mm thick Local RAJIM/ Red Flag stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid over & jointed with grey cement slurry mixed with pigments to match the shade of the stone i/c grinding, rubbing and polishing.	169.00	Sqm
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	13.26	Cum


Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub-Engineer
Municipal Corporation
Bhilai