

**MUNICIPAL CORPORATION OF BHILAI**  
**NIT**


वार्ड क्र. 44 लक्ष्मी नारायण नगर के विभिन्न स्थानों पर नाली निर्माण एवं सीमेंटीकरण कार्य।

(As Per PWD Building & Road SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	42.00	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	84.00	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	28.00	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	630.00	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	57.75	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	1732.50	Kg
7	Carriage by mechanical transport for 5 km lead. Earth	100.80	Cum
8	<u>Road SOR 01.01.2015</u> Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads )		
	P.C.C. M-25	108.00	Cum

  
**Executive Engineer**  
Municipal Corporation  
Bhilai

**Assistant Engineer**  
Municipal Corporation  
Bhilai

  
**Sub Engineer**  
Municipal Corporation  
Bhilai