

MUNICIPAL CORPORATION BHILAI

NIT

वार्ड क्रमांक 53 सेक्टर 01 के विभिन्न स्थानों में आर.सी.सी नाली के ऊपर आर.सी.सी. कवर लगाने का कार्य।

As Per PWD Building SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	126.50	Cum
2	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	7590.00	Kg



कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई



सहायक अभियन्ता
नगर पालिक निगम, भिलाई



उप अभियन्ता
नगर पालिक निगम, भिलाई