

MUNICIPAL CORPORATION OF BHILAI
NIT

वार्ड क्र. 39 स्वीपर मोहल्ला में नाली निर्माण एवं संधारण कार्य।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	5.60	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose including dressing and leveling of pits. In all types of soil.	25.20	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	6.30	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	112.00	Sqm
5	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1 1/2 :3	13.30	Cum
6	Filling from available excavated stuff in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50M and lift upto 1.5M.	5.60	Cum
7	Carriage by mechanical transport for 5 km lead. Earth	20.16	Cum



Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai