## MUNICIPAL CORPORATION OF BHILAI

## NIT

वार्ड क्र. 45 बालाजी नगर, छोटू सायकल स्टोर्स के पीछे एवं विभिन्न गलियों में सीमेंटीकृत मार्गों का संधारण कार्य।

As Per PWD Building & Road SOR 01.01.2015

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	437.50	Sqm
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	21.88	Cum
3	Carriage by mechanical transport upto 5 km lead:	21.88	Cum
4	Providing and laying cement concrete for plain concrete/reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-25	65.63	Cum

Executive Engineer Municiapal Corporation Bhilai Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer

Municipal Corporation

Bhilai