

MUNICIPAL CORPORATION OF BHILAI

नाम :- जोन कं. 05 अंतर्गत वार्ड कं. 58 सेक्टर 4 सड़क 26 गार्डन में पेवर ब्लॉक लगाने का ^{NIT} ^{कं. सामने} ^{खर्चा}

| S.N. | PARTICULARS OF ITEMS | Quantity | UOM |
|------|---|----------|-----|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal | 70.80 | cum |
| 2 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 35.04 | Cum |
| 3 | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, tamping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks | 350.40 | SQM |
| 4 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 3.86 | Cum |
| 5 | Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth | 70.80 | Cum |


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


Sub Engineer
Municipal Corporation
Bhilai (C.G.)