

**MUNICIPAL CORPORATION BHILAI (C.G.)****NIT****me of work :-** वार्ड कं. 63 सेक्टर 6 पश्चिम विभिन्न स्थानों में नाली एवं पुलिया निर्माण कार्य।

S.No.	Description and details of work	As per Building SOR 01.01.2015	
		Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soils	377.3	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level I excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	47.2	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work 1:11/2:3 (1cement :11/2 coarse sand :3 graded stone aggregate 20 mm nominal size).	90.6	Cum
4	Providing and placing in position reinforcement for RCC work including straightening cutting, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete Thermo-Mechanically treated bars FE 500D	4929.6	Kg
5	Providing and fixing form work in including centring ,shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	918.7	sqm
6	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	275.7	Cum

EXECUTIVE ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

ASSISTANT ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)