

**MUNICIPAL CORPORATION BHILAI  
NIT**

**NAME OF WORK -** जोन कं 05 अंतर्गत वार्ड कं.69 सेक्टर 9 के विभिन्न स्थानों मे नाली संधारण कार्य।

**PWD BUILDING SOR 01.01.2015**

No.	I/No.	Particular's Item	QTY	Unit
1	2	3	4	5
1	16.43.2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	24.00	Cum
2	1.26.3	Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba)As Per Item No. 01 Qty.	24.00	Cum
3	1.1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	319.13	Cum
4	1.26.1	Carriage by mechanical transport upto 5 km lead: Earth As Per Item No. 03 Qty.	319.13	Cum
5	3.1.2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	32.90	
6	3.2.1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). BOTTAM SLAB WALL TOP SLAB	101.40	Cum
7	3.12.1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415 DRAIN COVER BLOCK	4788.00	Kg
8	2.1.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. BOTTAM SIDE WALL SLAB BOTTAM SLAB SIDE	978.00	Sqm

  
**EXECUTIVE ENGINEER  
MUNICIPAL CORPORATION  
BHILAI**

  
**ASSISTANT ENGINEER  
MUNICIPAL CORPORATION  
BHILAI**

  
**Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)**