


MUNICIPAL CORPORATION BHILAI (C.G.)


NIT

कार्य का नाम :- वार्ड-11 सड़क नं. 18/बी शिव निषाद घर से पटेल किराना स्टोर तक नाली संधारण कार्य

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	22.56	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	28.20	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	9.40	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	244.40	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	26.32	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	2105.60	KG
7	Carriage by mechanical transport for 5 km lead.	22.56	Cum


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)