

MUNICIPAL CORPORATION BHILAI (C.G.)
NIT

कार्य का नाम :-वार्ड-11 फरीद नगर चिन्ताराम होटल से शिव मंदिर चौक तक नाली संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	191.16	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	31.86	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	67.26	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	5380.80	KG
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	566.40	Sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	28.32	Cum
7	Carriage by mechanical transport for 5 km lead.	191.16	Cum

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Rashmi
Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Rajesh
Sub. Engineer
Municipal Corporatio
Bhilai (C.G)

