

MUNICIPAL CORPORATION BHILAI (C.G.)
NIT

कार्य का नाम :- वार्ड-17 चिमरी पास सुदामा के घर के सामने नाली संधारण कार्य
शेड रेमेडिएशन के तहत भवन की लाइन तक नाली निर्माण कार्य
Pw Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	21.78	Cum
2	Demolishing cement concrete including disposal of material within 50 meter lead. 1:4:8	32.31	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	67.76	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	36.30	Cum
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	1016.40	Sqm
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	104.06	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	5203.00	KG
8	Carriage by mechanical transport for 5 km lead.	97.77	Cum

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Rashmi
Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Pankaj
Sub. Engineer
Municipal Corporatio
Bhilai (C.G)