


**MUNICIPAL CORPORATION BHILAI (C.G.)
NIT**


कार्य का नाम :-वार्ड-17 नेहरू भवन में अब्दुल मंजीद के घर के पीछे नाली संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	6.05	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	45.00	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	11.25	Cum
4	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 150 mm dia pipe.	250.00	Metre
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.25	Cum
6	Providing and constructing brick masonry road gully chamber 50x45x60 cm with well burnt modular clay bricks crushing strength not less than 35kg/cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	36.00	Nos

**Executive Engineer
Municipal Corporation
Bhilai (C.G)**


**Asstt. Engineer
Municipal Corporation
Bhilai (C.G)**


**Sub. Engineer
Municipal Corporatio
Bhilai (C.G)**