


MUNICIPAL CORPORATION OF BHILAI


NIT


कार्य का नाम :- वार्ड कं. 70 हुडेकोमें एमआइजी.-2 456 से एमआइजी.-2 412 तक आर.सी. सी नाली एवं स्लैब निर्माण कार्य।

(Based on PWD Building SOR Wef from Dated 01-01-2015)

S. No.	DESCRIPTION	QTY	UNIT
		3	4
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	2.26	cum
2	Carriage by mechanical transport upto 5 km Lead : Dismantled Building debris (Mulba)	2.26	cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	145.89	cum
4	Carriage by mechanical transport upto 5 km lead: Earth As Per Qty. Item No. (3)	145.89	cum
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	15.04	Cum
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). BOTTOM SLAB, WALL, TOP SLAB	38.12	Cum
7	Providing and placing in position reinforcement for RCC work including straightening cutting, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete Thermo-Mechanically treated bars FE 415 DRAIN COVER BLOCK	1756.26	Kg
8	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	433.20	Sqm


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


Sub Engineer
Municipal Corporation
Bhilai (C.G.)