

## MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

Name of work :- वार्ड कं. 59 सेक्टर 05 अडक -12 से 14 मध्य पौर ब्लॉक संवारण कार्य।

PWD SOR 01.01.2015 and NON SOR item			
S.No.	Description and details of work	unit	Qty.
1	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressivestrength of 250 kg/sq.cm 12.65.1 Plain/ normal coloured precast interlock concrete block	sqm	50.00
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	2.00
<b>NON SOR</b>			
1	Removing or replacing broken precast interlock concrete block with removed or new Plain/ normal coloured precast interlock concrete block approved size, make, colour, shade laid on 10 mm thick sand/dust base including removing the broken tile and mortar, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete including locking with 1.1.5.3 concrete mix 10cm wide and 10cm depth.	sqm	844.00
			TOTAL A + B
SAY TOTAL Rs.			



Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)



Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)