

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

As Per PWD Building SOR 01.01.2015

Name of work :- वार्ड कं. 57 सेक्टर 4 पूर्व सड़क 08 गार्डन के समीप एवं सड़क 30 ब्लॉक 09 डी के समीप में चेकर टाईल्स संधारण कार्य।

S.No.	Description and details of work	Qty.	unit
1	Demolishing cement concrete including disposal of material within 50 metre lead 1:3:6 or richer mix	37.80	cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	37.80	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 1 coarse sand : 4 graded stone aggregate nominal size).	18.90	cum
4	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) : Light shade using white cement	189.00	sqm
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2.76	cum
6	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	75.60	cum


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


Sub Engineer
Municipal Corporation
Bhilai (C.G.)