

MUNICIPAL CORPORATION BHILAI


NIT

NAME OF WORK - जोन कं 05 अंतर्गत वार्ड कं. 70 हुड़को शहीद कौशल के घर के पास नाली संधारण कार्य।

PWD BUILDING SOR 01.01.2015

| No. | I/No. | Particular's Item | QTY | Unit |
|-----|---------|---|--------|------|
| 1 | 2 | 3 | 4 | 5 |
| 1 | 16.43.2 | Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix | 1.88 | Cum |
| 2 | 1.26.3 | Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba)As Per Item No. 01 Qty. | 1.88 | Cum |
| 3 | 1.1.1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. | 54.71 | Cum |
| 4 | 1.26.1 | Carriage by mechanical transport upto 5 km lead: Earth As Per Item No. 03 Qty. | 54.71 | Cum |
| 5 | 3.1.2 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | 5.64 | Cum |
| 6 | 3.2.1 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). BOTTAM SLAB WALL TOP SLAB | 15.32 | Cum |
| 7 | 3.12.1 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415 DRAIN COVER BLOCK | 730.26 | Kg |
| 8 | 2.1.1 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. BOTTAM SIDE WALL SLAB BOTTAM SLAB SIDE | 170.40 | Sqm |


 ASSISTANT ENGINEER
 MUNICIPAL CORPORATION
 BHILAI


 Sub Engineer
 Municipal Corporation
 Bhilai (C.G.)