

(2) (7)


NAGAR NIGAM BHILAI

NIT

घायक निधि अंतर्गत वार्ड क्र.-16 रावणभाठा सुपेला में सार्वजनिक सांस्कृतिक मंच निर्माण कार्य।

(AS PER PWD BUILDING S.O.R 01.01.2015)

S.NO	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or forupto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soil	16.28	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.		
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	6.84	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	17.07	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:		
	Thermo-Mechanically treated bars FE 415	1706.68	kg
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
5.a	Foundations, footings, base of columns and plinth beam in any shape and size.	23.68	sqm
5.b	Columns, Pillars, Piers and likes- rectangular or square in shape	56.80	sqm
5.c	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	98.51	sqm
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:		
	Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	3.96	cum
7	super structure Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in::		
	Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	11.74	cum
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		25.52	cum
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork		
		0.24	sqm
10	Providing and fixing steel door with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer..		
		42.00	kg
11	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat of red oxide zinc chromate primer..		
		210.00	kg

12	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals .. locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.		
		4.20	
13	6 mm thick cement plaster of mix:		
	In Cement Mortar 1:4 (1 cement : 4 fine sand)	68.52	sqm
14	12mm thick cement plaster of mix:		
	In Cement Mortar 1:6 (1 cement : 6 fine sand)	85.20	sqm
15	15mm thick cement plaster of mix:		
	In Cement Mortar 1:6 (1 cement : 6 fine sand)	114.00	sqm
16	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.		
		48.56	sqm
17	Distemping with acrylic washable distemper to give an even shade:		
	on new work.(two or more coats)	153.72	sqm
18	Painting new exterior surface (two or more coats) with PREMIUM TEXTURED paint as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:		
	On new work (Two or more coats)	114.00	sqm
19	Painting on new work (two or more coats) to give an even shade with.		
	Premium synthetic enamel paint (2nd top most approved branded quality) to give an even shade .		
		21.36	sqm
20	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of ..1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.		
	Size upto 200x300mm	28.40	sqm
21	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.		
	SS Grade 204	50.00	KG
22	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse.. fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm		
	Pigment Coloured (rubber mould) precast interlock concrete blocks		
		56.00	KG
			
ASSTT.ENGINEER Nagar Palik Nigam, Bhilai		SUB ENGINEER Nagar Palik Nigam, Bhilai	