

MUNICIPAL CORPORATION OF BHILAI
NIT

वार्ड क्र. 48 तिरंगा नगर, सड़क 12 के पास स्थित चबूतरों तथा पंप हाउस मैदान स्थित सामुदायिक भवन का संधारण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	7.20	Cum
2	Providing and laying rectified ceramic glazed floor tiles of size 300x300mm and above conforming to IS : 15622 of approved make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	9.00	Sqm
3	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	54.40	Sqm
4	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	224.00	Sqm
5	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade. On old work (one or more coats)	369.75	Sqm
6	25mm thick cement concrete flooring with 1:2:4 cement concrete (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with floating cost of neat cement.	60.00	Sqm
7	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	3.00	Cum
8	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	4.80	Cum
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.20	Cum
10	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1 ½ :3 (1 cement : 1 ½ coarse sand : 3 graded stone aggregate 20mm nominal size)	5.40	Cum
11	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars.	378.00	Kg
12	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Wall of any thickness including attached pilasters, buttresses etc. in super structure.	28.80	Sqm
13	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	10.80	Cum

SN	PARTICULERS OF ITEMS	QTY.	UNIT
14	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.44	Cum
15	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	7.20	Sqm
16	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete. SS Grade 304	137.44	Kg
17	Add Extra For Electrification Work	10000.00	LS


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai