MUNICIPAL CORPORATION BHILAI

NAME OF WORK - जोन कं 05 अंतर्गत वार्ड कं. 65 सेक्टर 10 सड़क 33 में नाली संघारण कार्य।

IN	lo.	Particular's Item		LDING SOR 01.01.2015	
	1 /No.	Action for all the second seco	I OTY I	Unit	
	-	Demolishing cement concrete including disposal of material within 50 metre	4	5	
F	16.43.2	Carriage by mechanical to	0.94	Cum	
2	1.26.3	Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba)As Per Item No. 01 Qty.	0.94	Cum	
3	1.1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	109.42	Cum	
4	1.26.1	Carriage by mechanical transport upto 5 km lead: Earth As Per Item No. 03 Qty.		Cum	
5	3.1.2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	11.28	Cum	
6	3.2.1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:11/2:3 (1 cement : 11/2 coarse sand : 3 graded stone aggregate 20mm nominal size). BOTTAM SLAB WALL TOP SLAB	27.00	Cum	
7	3.12.1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415 DRAIN COVER BLOCK	1275.30	Kg	
8	2.1.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. BOTTAM SIDE WALL SLAB BOTTAM SLAB SIDE	321.80	Sqm	

ASSISTANT-ENGINEER
MUNICIPAL CORPORATION
BHILAI

Sub Engineer Municipal Corporation Bhilai (QG.)