

①

## MUNICIPAL CORPORATION BHILAI (C.G.)


### NIT


कार्य का नाम :- वार्ड-07 राधिका नगर के सीवर लाईन चेम्बर में ढक्कन संधारण कार्य।


(As per P.W.D BUILDING S.O.R. 01.01.2015)

15)

S.No.	Description and details of work	Qty.	Unit
1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	43.80	Cum
2	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars	1752.00	Kg

  
Executive Engineer  
Municipal Corporation  
Bhilai (C.G)

  
Asstt. Engineer  
Municipal Corporation  
Bhilai (C.G)

  
Sub. Engineer  
Municipal Corporatio  
Bhilai (C.G)