

MUNICIPAL CORPORATION BHILAI (C.G.)
NIT


कार्य का नाम :-वार्ड-06 संजय नगर में नाली निर्माण कार्य।

Pwd Building Sor 01.01.2015

| No. | Description and details of work | Qty. | Unit |
|-----|--|---------|------|
| 1 | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil. | 286.00 | Cum |
| 2 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 35.75 | Cum |
| 3 | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3 | 87.75 | Cum |
| 4 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars. | 6142.50 | KG |
| 5 | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size | 845.00 | Sqm |
| 6 | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M. | 39.00 | Cum |
| 7 | Carriage by mechanical transport for 5 km lead. | 286.00 | Cum |


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)