

**MUNICIPAL CORPORATION, BHILAI
NIT**

कार्य का नाम:- वार्ड क्रमांक 36 केम्प-02, महात्मा गांधी नगर के विभिन्न स्थानों में
पाईप लाईन संधारण एवं नवीनीकरण का कार्य।
(As per P.W.D. Building S.O.R. W.E.F. 01.01.2015)

S.No.	Details of Item	UOM	Quantity
1	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: 15mm dia. nominal bore (Page- 177, Item-19.9.1) 15mm dia nominal bore	MTr	63.00
2	20mm dia. nominal bore (Page- 177, Item-19.9.2)	MTr	180.00
3	25mm dia. nominal bore (Page- 177, Item-19.9.3)	MTr	180.00
4	32 mm dia. nominal bore	MTr	180.00
5	Making connection of G.I. distribution branch in G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete: (Dia of main line to be measured) 50 mm nominal bore	Nos	10.00
6	Providing and fixing brass/gun metal gate valve with C.I. wheel of approved quality (screwed end): 50mm nominal bore.	Nos	20.0
7	Providing and fixing 15mm nominal bore Brass bib/stop cock of approved quality : Bib cock (350gram)	Nos	10.0
8	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore	Nos	2.0
9	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 32 mm nominal bore	Nos	3.0
10	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc.and testing of joints complete:32 mm dia. nominal bore	Nos	2.0

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई