MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :- वार्ड क्रमांक 56 सेकटर 02 दुर्गा मंच में शेड संधारण कार्य।

As Per PWD Building SOR 01.01.2015

	As Per PWD Building SOK 01.01.2013			
SN.	Details of Item	Qty.	Unit	
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	0.96	Cum	
2	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming toIS:12894-2002 of class designation 4.0 in foundation and plinth in:Cement Mortar 1:6 (1 cement : 6 coarse sand)	0.96	Cum	
3	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	96.00	Sqm	
4	Painting on new work (two or more coats) to give an even shade with:Satin synthetic enamel paint	36.00	Sqm	
5	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	41.50	Sqm	
6	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zincchromate primer. Electric resistance or induction butt welded tubes Grade-250	400.00	КG	
7 (1) (1) (1) (1) (1) (1) (1) (1	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/-5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and solvester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /selftapping screws of size 5.5x 55mm) with EPDM seal or with polymercoated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. impet washers filled with white lead completeupto any pitch in a corizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including sutting to size and shapewherever required.	36.00	Sqm	

कार्यपालन अभियन्ता नगर पालिक निगम, भिलाई

सहर्यके\अभियन्ता नगर पालिक निगम, भिलाई

नगर पालिक निगम, भिलाई