


MUNICIPAL CORPORATION BHILAI (C.G.)


NIT

Name of work :- सेक्टर 05 स्थित सड़क 12-13 के मध्य में डोम शेड का सौंदर्यीकरण कार्य।

As per Building SOR 01.01.2015

| S.No. | Description and details of work | Qty. | unit |
|-------|---|--------|------|
| 1 | 15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above) | 308.00 | sqm |
| 2 | providing and making 12mm thick cement plaster of mix:n Cement Mortar 1:6 (1 cement : 6 fine sand) | 30.00 | sqm |
| 3 | Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. 14.11.1 On new work (two or more coats) | 30.00 | sqm |
| 4 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 20.0 | Cum |
| 5 | Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.9.57.1 SS Grade 204 | 200.0 | kg |
| 6 | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm | 10.00 | sqm |
| 7 | Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.On old work (one or more coats) | 50.00 | sqm |
| 8 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 3.0 | Cum |
| 8 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 20mm nominal size). | 20.0 | Cum |
| 11 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for | 20 | sqm |
| 12 | Premium synthetic enamel paint | 70 | sqm |


Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)


Sub Engineer
Municipal Corporation
Bhilai (C.G.)