

5

MUNICIPAL CORPORATION -BHILAI

NIT

कार्य का नाम :- जोन कं. 05 अंतर्गत सेक्टर 10 वार्ड कं. 64 में जयंती स्टेडियम के समीप स्थित कुएं का संधारण कार्य।

As per C.G PWD Building sor w.e.f- 01-01-2015

| S/NO. | PARTICULARS | QTY. | UNIT |
|-------|--|--------|------|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil | 63.63 | Cum |
| 2 | Extra for every additional lift of 1.5 m or part thereof. All types of soil | 222.71 | Cum |
| 3 | Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water. | 190.89 | Cum |
| 4 | Extra rate for quantity of work executed in or under foul condition | 63.63 | Cum |
| 5 | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 8.19 | Cum |
| 6 | Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 8.19 | Cum |
| 7 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars | 655.20 | Kg |
| 8 | Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: wall | 63.63 | Sqm |
| 9 | Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, Pillars, Piers and likes- rectangular or square in shape | 3.00 | Sqm |
| 10 | Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) | 1.80 | Cum |
| 11 | Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size above 200x300mm | 18.00 | Sqm |
| 12 | 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand) | 150.00 | Sqm |
| 13 | Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats) As per item No.-19 | 90.00 | Sqm |
| 14 | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer. | 380.00 | KG |


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI