


MUNICIPAL CORPORATION BHILAI


NIT

NAME OF WORK - जोन कं 05 अंतर्गत वार्ड कं. 65 सेक्टर 10 सड़क 33 में नाली संधारण कार्य।

PWD BUILDING SOR 01.01.2015

No.	I/No.	Particular's Item	QTY	Unit
		3	4	5
1	2			
1	16.43.2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	0.94	Cum
2	1.26.3	Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba) As Per Item No. 01 Qty.	0.94	Cum
3	1.1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	109.42	Cum
4	1.26.1	Carriage by mechanical transport upto 5 km lead: Earth As Per Item No. 03 Qty.	109.42	Cum
5	3.1.2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	11.28	Cum
6	3.2.1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). BOTTAM SLAB WALL TOP SLAB	27.99	Cum
7	3.12.1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415 DRAIN COVER BLOCK	1275.30	Kg
8	2.1.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. BOTTAM SIDE WALL SLAB BOTTAM SLAB SIDE	321.80	Sqm


 ASSISTANT ENGINEER
 MUNICIPAL CORPORATION
 BHILAI


 Sub Engineer
 Municipal Corporation
 Bhilai (C.G.)