



MUNICIPAL CORPORATION OF BHILAI
NIT

नाम :- वार्ड कं. 63 सेक्टर 06 पश्चिम सड़क 61 के समीप मंच संधारण

No.	DESCRIPTION	(Based on PWD Building SOR Wef from Dated 01-01-2015)	
		QTY	UNIT
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	1.20	cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	2.70	cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	3.36	cum
4	Carriage by mechanical transport upto 5 km lead: Earth As Per Qty. Item No. (1)	7.26	cum
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.62	Cum
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	3.50	Cum
7	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	5.60	Sqm
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	6.80	Cum
9	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	22.80	Sqm
10	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	21.00	Cum
11	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm thick	28.00	Sqm


Asstt. Engineer
Municipal Corporation
Bhilai (C.G.)


Sub Engineer
Municipal Corporation
Bhilai (C.G.)