NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्र.–15 अम्बेडकर नगर मीना देवी निवास से हनुमान मंदिर तक रोड संधारण कार्य।

(As per P.W.D BUILDING / ROAD S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	QTY	UNIT
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	1.80	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads		
	P.C.C. M-10	0.60	cum
	P.C.C. M-30	91.52	cum

ASSISTANT ENGINEER
NAGAR PALIK NIGAM, BHILAI

SUB ENGINEER
NAGAR PALIK NIGAM, BHILAI

EXECUTIVE ENGINEER
Nagar Palik Nigam, Bhilai