

MUNICIPAL CORPORATION -BHILAI

NIT

कार्य का नाम :- जोन कं. 05 अंतर्गत सेक्टर 10 वार्ड कं. 64 में जयंती स्टेडियम के समीप स्थित कुएं का संधारण कार्य।

As per C.G PWD Building sor w.e.f- 01-01-2015

S/NO.	PARTICULARS	QTY.	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	63.63	Cum
2	Extra for every additional lift of 1.5 m or part thereof. All types of soil	222.71	Cum
3	Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water.	190.89	Cum
4	Extra rate for quantity of work executed in or under foul condition	63.63	Cum
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	8.19	Cum
6	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	8.19	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	655.20	Kg
8	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: wall	63.63	Sqm
9	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, Pillars, Piers and likes- rectangular or square in shape	3.00	Sqm
10	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1 80	Cum
11	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size above 200x300mm	16.00	Sqm
12	15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	150.00	Sqm
13	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats) As per item No.-19	90.00	Sqm
14	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	380.00	KG

EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI

ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI

SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI