

MUNICIPAL CORPORATION BHILAI (C.G.)

Name of work :- *प्रा. सं. 57 सोकर-04 पूरा के विभिन्न स्थानों में*  
 NIT *के लिए*

As per Building SOR2015/ELEC sor 2020

S.No.	Description and details of work	Qty.	unit
1	Providing corrugated G.I. sheet roofing including vertical/ curved surfaces fixed with galvanized iron, J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead including painting with primer and paint on overlapping of sheets complete excluding the cost of purlins rafters and trusses. (Zinc coating not less than 272 gms/sqm)	300.0	sqm
2	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete:	252.0	m
3	Providing and laying nominal mix plain cement concrete with crushedstone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.5	cum

*[Signature]*  
 Asstt. Engineer  
 Municipal Corporation  
 Bhilai(C.G.)

*[Signature]*  
 Sub Engineer  
 Municipal Corporation  
 Bhilai (C.G.)