

①

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम – मुख्य कार्यालय में विभिन्न कक्ष का संधारण कार्य।

| S.N. | SOR | PARTICULERS OF ITEMS | No | L | B | H/D | Quantity |
|------|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|------|-----------------|----------|
| 1 | 8.22 | Providing and fixing paneling in paneled or paneled and glazed shutters for doors etc. (only area of paneling to be measured). Paneling for or paneled and glazed shutters 25 mm to 40 mm thick: | | | | | |
| | 8.22.9 | 12 mm thick solid PVC sheet with decorative lamination on both sides of approved quality and make | 8 | 3 | 4.00 | | 96.0 |
| | | | | | | G. Total | 96.0 |
| 2 | 10.63 | Providing and fixing 97mm thick Gypsum board partition upto ceiling height consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120, consisting of floor and ceiling channel 50mm wide having equal flanges of 32mm and 0.55mm thick fixed to the floor and ceiling at the spacing of 610mm centre to centre with dash fastener of 12.5mm diameter 40mm length and the studs 48mm wide having one flange of 34mm and other flange 36mm and 0.55mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610mm centre to centre by 6mm dia bolts and nuts at both ends of partition fixed flush to wall with rawl plugs at spacing of 450mm centre to centre and fixing of boards to either side of frame work by 25mm dry wall screws on studs, floor and ceiling channels at the spacing of 300mm centre to center and 97mm thick Gypsum board which includes one layer of tapered edge 12.5mm thick Gypsum plaster board (conforming I.S. 2095-1982) screw fixed with 25mm screws at 300mm centre to centre to either side, including jointing and finishing to a flush | 12 | 5 | 4 | | 240.0 |
| | | | | | | G. Total | 240.00 |

(2)

| | | | | | | |
|-----------------|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|----|---|--------------|
| 3 | 16.37 | Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead. | 1 | 10 | 2 | 20.00 |
| G. Total | | | | | | 20.00 |
| 4 | 17.1 | Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead | | | | |
| | 17.1.1 | Thickness upto 15mm | 1 | 10 | 3 | 30.00 |
| G. Total | | | | | | 30.00 |

सहायक अभियंता
नगर पालिक निगम
भिलाई


उप अभियंता
नगर पालिक निगम
भिलाई