

**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**

कार्य का नाम :-वार्ड-09 एकता द्वारा सैयद बाबा मजार के पास नाली एवं पुलिया संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	14.64	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	33.60	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	10.15	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	229.50	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	23.94	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	1214.85	KG
8	Carriage by mechanical transport for 5 km lead.	40.32	Cum
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.80	Cum

**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

*R. Ashwin*  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

*[Signature]*  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**

