

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- वार्ड-03 मॉडल टाउन में आंगनबाड़ी के सामने स्थित मंच का संधारण कार्य।

Pwd Building Sor 01.01.2015 & Electric Sor 01.06.2020

S.No.	Description and details of work	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	2.40	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	25.61	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.03	Cum
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	16.123	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	1612.25	Kg
6	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	(A) Foundations, footings, base of columns and plinth beam in any shape and size.	21.66	Sqm
	(B) Columns. Pillars. Piers and likes rectangular or square in shape	23.10	Sqm
	(C) Beams, lintels, cantilevers & walls	8.84	Sqm
	(D) Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	58.26	Sqm
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	21.23	Cum
8	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in :Cement Mortar 1:6	2.65	Cum
9	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	3.83	Cum
10	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	44.88	Sqm
11	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	19.14	Sqm

12	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	19.14	Sqm
13	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm thick	38.38	Sqm
14	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	19.14	Sqm
15	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)	44.88	Sqm
16	Add Extra for Electrification	5000.00	RS

**Executive Engineer
Municipal Corporation
Bhilai (C.G)**

**Asstt. Engineer
Municipal Corporation
Bhilai (C.G)**

**Sub. Engineer
Municipal Corporatio
Bhilai (C.G)**