



MUNICIPAL CORPORATION OF BHILAI
NIT


वार्ड क्रमांक 53 सेक्टर 01 वेलकम गेट के सामने में पेवर ब्लॉक संधारण कार्य

As Per PWD Building SOR 01.01.2015

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing cement concrete including disposal of material within 50 metre lead.1:3:6 or richer mix	11.60	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	11.60	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2.64	Cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Plain/ normal coloured precast interlock concrete block	116.00	sqm
5	Carriage by mechanical transport upto 5 km lead: Earth	11.60	sqm


कार्यपालन अभियन्ता
नगर पालिक निगम, गिलाई


सहायक अभियन्ता
नगर पालिक निगम, गिलाई


उप अभियन्ता
नगर पालिक निगम, गिलाई