## MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :— पार्षद निधि (वर्ष 2021–22) से वार्ड–05 यादव मोहल्ला, मराठी मोहल्ला एवं विभिन्न स्थानों में सी.सी. रोड एवं नाली निर्माण कार्य।

Pwd Building & Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-25	65.63	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	27.00	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	4.50	Cum
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	9.50	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	855.00	KG
6	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: a)Foundations, footings; base of columns and plinth beam in any shape and size	80.00	Sqm
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	4.00	Cum
8	Carriage by mechanical transport for 5 km lead.	27.00	Cum

Executive Engineer Municipal Corporation Bhilai (C.G)

-

Asstt. Engineer Municipal Corporation Bhilai (C.G) Sub. Engineer Municipal Corporatio Bhilai (C.G)