## MUNICIPAL CORPORATION BHILAI (C.G.)

## **NIT**

कार्य का नाम :- पार्षद निधि से वार्ड-18 कान्ट्रेक्टर कॉलोनी सत्संग विहार के पास हरा मैदान का उद्यान के रूप में उन्नयन कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	9.00	Cum
2	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 200 mm diameter	30.00	Metre
3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 200 mm diameter S.W. pipe	30.00	Metre
4	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	3.56	Cum
5	Painting on new work (two or more coats) to give an even shade with:	522.15	Sqm
6	Floor painting with superior quality enamel paint to give an even shade.  On new work (two or more coats)	510.000	Sqm
7	Tree Guard with MS Angle Iron and Steel Wire (Providing and fixing tree guard 0.60 meter square, 2.00 meter high fabricated with MS angle iron 30 x 30 x 3 mm, MS iron 25 x 3 mm at 100mm centre to centre and steel wire 3 mm dia. welded and fabricated as per design in two halves bolted together, fixed in ground with P.C.C M-10 of dimensions 150x150x200mm.)	7.000	Each

**Executive Engineer Municipal Corporation** Bhilai (C.G)

**Municipal Corporation** Bhilai (C.G)

Sub. Engineer **Municipal Corporatio** Bhilai (C.G)