

# MUNICIPAL CORPORATION OF BHILAI

## NIT

कार्य का नाम :- वार्ड क्रमांक 54 सेक्टर 01 स्वामी विवेकानंद गार्डन में फाउण्टेन  
संधारण कार्य।

As Per PWD Building SOR 01.01.2015

S.N	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.In all types of soil	144.00	Cum
2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).In all types of soil	346.50	Sqm
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	61.88	Cum
4	Painting on new work (two or more coats) to give an even shade with:Satin synthetic enamel paint	330.00	sqm
5	Carriage by mechanical transport upto 5 km lead:Earth	140.00	sqm

कार्यपालन अभियन्ता  
नगर पालिक निगम, मिलाई

सहायक अभियन्ता  
नगर पालिक निगम, मिलाई

उप अभियन्ता  
नगर पालिक निगम, मिलाई