



**MUNICIPAL CORPORATION BHILAI  
NIT**


**कार्य का नाम – वार्ड क्रमांक 35 एवं 33 के मध्य आर.सी.सी. पुलिया एवं  
नाली के स्लोप संधारण कार्य।**

**AS Per PWD Building SOR 01.01.2015**

SN	Details of Item	Qty.	Unit
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	4.56	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	9.60	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	1.20	Cum
4	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	7.28	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	582.40	Kg
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	6.00	Cum
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	38.40	Sqm
8	Carriage by mechanical transport for 5 km lead.	14.16	Cum

  
कार्यपालन अभियन्ता  
नगर पालिक निगम, मिलाई

  
सहायक अभियन्ता  
नगर पालिक निगम, मिलाई

  
उप अभियन्ता  
नगर पालिक निगम, मिलाई